



Track Markings for Respray

1. Relay Zones –Paint each of the 4 zones Grey
2. Paint standard waterfall start line at start-finish line
3. Paint staggered alley start lines in the outer lanes (4,5,6) (7,8,9) (same as current markings).
4. Paint distance markers along both long jump runways (same as current markings).
5. Paint pole plant distance markers along both pole vault runways. Continue markings down to the plant box (13ft down to 4ft).
6. 1500m Waterfall start line
7. The District has engaged with AstroTurf Corporation to procure the Rekortan RS Track Surfacing material and will have it available for the selected contractor on or before the first day of construction.
8. Refer to the Rekortan RS WB Specification for requirements for all bidders.