



Proposal

Project Name: CUSD Ambuehl ES HVAC

Bid Date: 02/16/2024

Location: San Juan Capistrano, CA 92675

Expiration Date: 03/15/2024

Attention: CMAS

Proposal Number: 1123MFAT0280C

Mark For	Qty	Model Number	Description
3Ton HP	9	50GCQJ04A2A5-3A0A0	Nominal 3Ton Heat Pump Rooftop Unit <ul style="list-style-type: none">Two-Stage Cooling single circuit (SEER)208/230-3-60Standard PackagingDirect drive, EcoBlue, medium static fanAl/Cu cond. coil - Al/Cu evap coilSystemVu Controller <i>Field Installed Accessories</i> <ul style="list-style-type: none">EconomizerPower ExhaustEconomizer Harness KitPitched Roof Curb (To be field verified by contractor prior to order) <i>Services & Warranties</i> <ul style="list-style-type: none">Complete Year 1-3 Parts & CCS Labor WarrantyEconomizer Controls Assistance
4Ton HP	5	50GCQJ05A2A5-3A0A0	Nominal 4Ton Heat Pump Rooftop Unit <ul style="list-style-type: none">Two-Stage Cooling single circuit (SEER)208/230-3-60Standard PackagingDirect drive, EcoBlue, medium static fanAl/Cu cond. coil - Al/Cu evap coilSystemVu Controller <i>Field Installed Accessories</i> <ul style="list-style-type: none">EconomizerPower ExhaustEconomizer Harness KitPitched Roof Curb (To be field verified by contractor prior to order) <i>Services & Warranties</i> <ul style="list-style-type: none">Complete Year 1-3 Parts & CCS Labor WarrantyEconomizer Controls Assistance
2Ton HP	1	50VR-K24---3	Nominal 2Ton Heat Pump SPP Rooftop Unit <ul style="list-style-type: none">208/230-1-60VStandard Heat <i>Field Installed Accessories</i> <ul style="list-style-type: none">Pitched Roof Curb (To be field verified by contractor prior to order)OSA HoodBACnet Controller & required controls components
	1	COORDINATION	Shipping, Storage & Coordination